



Rapid Technologies to Enhance Quality Control on Asphalt Pavements Infrared (IR) Scanner Workshop

Hosted by Maine DOT April 28, 2016



AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS







Workshop Objective

- 1. Describe the Infrared Scanner Technology (What is it and Why it is needed?)
- 2. Understand how to use the IR Equipment & Software
- 3. Discuss the results from the Maine DOT
- 4. Discuss the Contractor's and Agency's Perspective as a QC or QA Tool
- 5. Know Implementation Strategies

Infrared Scanner Workshop

AGENDA:

8:30 to 8:45	Welcome and Introductions
8:45 to 9:15	 Introduction to Infrared Technology: What is it and Why is it Needed?
9:15 to 9:30	Equipment and Software: How to use it?
9:30 to 10:00	Data Analyses and Findings
10:00 to 10:15	Break
10:15 to 10:45	Agency Perspective as a QA Tool
10:45 to 11:15	Contractor's Perspective as a QC Tool
11:15 to 12:00	Implementation Strategies
12:00 to 12:25	Questions/Answers and Closing Comments
12:25 to 12:30	IR Workshop Wrap-Up
12:30 to 1:00	Presentation and Demonstration of GPR Equipment





Infrared Technology (IR)

What is it and why use it?

April 28, 2016




1. IR - Defined.

- 2. How is it measured?
- 3. Why is it important?


Infrared Thermography:


- The mapping of temperature contours (equal temperature) over the surface of a material.
- Contours are used to evaluate materials by measurement of their surface temperature and its variation.



Temperature segregation (differential):


 More than 25 °F difference in mat temperature behind screed.






Types of Temperature Differences:

- 1. Cold spots
 - Truck to truck temperature differences
 - Improper loading and unloading of trucks
- 2. Thermal streaks
 - Longitudinal segregation
 - Inadequate or non-uniform amount of material across the mat



16/08/06 09:13:43 e=0.97


- Cold spots
 - Temperature difference of mat between truck exchanges – common.
 - Areas with higher air voids
- Focused testing have validated higher air voids
 - Coring
 - Radar (full coverage)
 - Nuclear gauge





Background

- 1996 through 2000s field work concluded temperature differences could be accurately detected and quantified:
 - Low temperatures result in low density zones in mat
 - A few States adopt temperature uniformity specification



Temperature profile criteria based on desired density uniformity.

- 1. IR Defined.
- 2. How is it measured?
- 3. Why is it important?

History; Mat Temperature Measurements

- Temperature guns
 - Point readings
- Temperature cameras
 - Time specific to identify areas with cold spots or thermal streaks




History; Mat Temperature Measurements

- IR sensors, IR-Bar; first device for continuous readings
- Pave-IR Scanner; second generation device for continuous readings



Application & use of temperature cameras


- Identify areas with cold spots for biased sampling in density specification
- Identify thermal streaks



Application & use of IR-Bar and Scanner


- Continuous readings to evaluate mat uniformity through temperature uniformity.
- Non-uniform temperatures usually mean, nonuniform densities.





- 1. IR Defined.
- 2. How is it measured?
- 3. Why is it important?

- Aggregate segregation in mat = temperature segregation
- Non-uniform temperatures usually result in non-uniform densities



Segregation – A difficult issue to resolve, when it is difficult to identify or confirm.



• Truck to truck segregation results in cold spots; IR can accurately identify these areas.




• Both sided longitudinal and centerline segregation result in thermal streaks; IR can identify these areas.




- Effect of cold spots, low mat temperatures on percent compaction; densities are:
 - Lower
 - More variable




• Effect of reduced compaction or higher air voids because of lower mat temperatures.



 Fatigue life can be substantially reduced, as a result of lower densities because of lower mat temperatures.



Impact of temperature differences or areas with low temperatures.







Cold spots; areas with increased potential for:

- Fatigue cracks
- Raveling
- Pot holes









Thermal streaks; longitudinal areas with increased potential for:

Longitudinal cracking





- Thermal streaks can be very damaging, depending on the level of density achieved in localized areas.
- Measuring the density, accurately, in a localized area is complicated.











NEXT:

• Equipment and Software: How to use it?





Infrared Technology (IR)

IR Equipment and Software: How to Use It?

April 28, 2015



AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS



- 1. Equipment and Installation
- 2. Software and Its Features

Equipment

- Mast Base
- Mast Extension
- Mast Arm
- IR Scanner
- DMI
- GPS Unit
- Wiring
- Connection bolts & materials



IR mast base and extension attached to paver.





- IR Scanner attached to paver; scans mat behind screed in one direction.
- GPS attached to the mast arm.




IR scan screen used to see/monitor mat temperatures in real time; attached to the mast post or extension.





DMI placed on wheel hub to measure distance during paving operation.





- 1. Equipment and Installation
- 2. Software and Its Features

Two models of data transfer and extraction





- Online Web App: https://eroutes.info/paveappweb/
- Login is user specific

් X ⊘ eRoutes :: PaveAppWeb X		
eRoutes ^{MC} Open a new session 		
Username: Pave-IR Password: •••••• Domain: Login Remember my username and domain	extended validation certificate	
YOUR INFORMATION, IN REAL TIME If you have come to this page while trying to a do not have the proper security for the other p logged in yet.	ccess another then you bage or you have not	


Please log in if you haven't. If you feel you should access an area but you can't, contact support immediately.


Explore Data: MOBA Pave Project Manager Main Screen

💐 Pave Project Mana	ger - Pave_2015-09-16-110725.p	oaveproj (Finished o	on 9/16/2015 9:22	AM)													
File View Repo	rt Extras Options Help																
🚔 🍏 🛠 🧧																	
Color Map 4 ×														Ψ×	Properties		Ψ×
407°F	969 968	967	966	965	964	963	962	961	960	959	958	957	956	955	Thermal Profile		-
				—				_					-		▲ Actions		
															Interpolation	Linear	
	Color Ma	an													Sample Spots of Inter Station		
		up													Stations Dooltip	Show Visible	
															✓ Profile View	1500	
															Ignored Sensors		
															Length	1513.78ft	
															Start Units	0.33/t Feet	
															Zoom	100.0%	
																–	
					— —	'l										Properties	
						nerr	nai	Prof	lle							Toperties	
										_						-	
	(P.			
61°F	.33ft													1514.11ft			
Project Propertie	Time Diagram Speed Dia	agram	ature Class Diagra	m										. ×	1		
Meta Information	Beginning location				houlton off									*			
	Comment				passing lan	e w/4shld											
Metrics	Ignored Sensors Layer thickness				1.5in									E			
	Lift				1.300		D '			l		4					
	Measure height				9.58ft			aora	ms a	and	prol	ecti	ntor	mati	on		
	MINDS Upload				No			~9.0									
	Operator Name				paul 11.48ft	_											
	Paving width Project ID					2-4b24-a035-3a7f4	6367793							-			
	Beginning location				67 0 00 T 00 T												
	The name of the location where the	he project began.															
															Interpolation		
														Save	Determines the kind of al	gorithm used when displaying the Profile.	


Сс	olor Map and Properties	for Screen	Color Map 4 × 407'F
Pro	operties		
Colo	or Map		
4	Temperature range		
	Max	407°F	
	Min	61°F	


Pave Project Man File View Rep B A A A A A A A A A A A A A A A A A A A	ort Extras Op		veproj (Finished c	on 9/16/2015 9:2.	2 AM)	-	Th	err	nal	P	rof	ile	e Properț	Ies Properties	Screen	
407'F	969	968	967	966	965	964	963	962	<u>961</u>	960	959		operties	Tipate		
												The	ermal Profile			
												⊿	Actions			
													Interpolation		Linear	
												\triangleright	Sample Spots of Interes	st	Enabled	
													Stations		Show	
												\triangleright	Tooltip		Visible	
												⊿	Profile View			
													Ignored Sensors			
													Length		1513.78ft	
													Start		0.33ft	
													Units		Feet	
													Zoom		100.0%	
	∢ 0.33ft es ∕Time Diagran	Smand Dise		atura Class Dian									• X			
Meta Information	Beginning loc		gram r remper	ature class blag		houlton of	ramp						•	1		
Metrics	Comment Ianored Sens					passing la	ne w/4shld									
Wettes	Layer thickne					1.5in							E.			
	Lift Measure heig					9.58ft										
	MINDS Uploa Operator Nan					No										
	Paving width					11.48ft	12 /1 24 - 025 2 7	40207702								
	Project ID Beginning loca					6/uruer1-e94	42-4b24-a035-3a7	14030//33								
	The name of the I	ocation where the	e project began.											Interpolation		
													Save		f algorithm used when displaying the Profile.	






File View R	Annager - Pave, 2015-09-16-110725, paveproj (Finished on 9/16/2015 9:22 AM) Lepot Extras Options Help Thermal Profile Thermal Profile Ther	[‡] X	Properties 4 X
407*F	969 968 967 966 965 964 963 962 961 960 959 958 957 956	955	Temperature Class Diagram General Show Percent Yes Target temper: 270 Temperature r. 20
			resperatues 20
50°F	۲ (► 1514.11ft	
Project Prope	rties V Time Diagram V Speed Diagram V Temperature Class Diagram V Map diagram	• ×	
	Speed Diagram		
	Paver Speed		
30 -			
25 -			
20 -	Man for a strain of the state of the	MMAA	
도 20 -		_	
t/mi	handling and the second and the second provided the second provided and the second provided and a second provided an		
Speed in [ft/min]	Ministration of the second and the s		
sed	New York Control of the Control of t		
<mark>ອ</mark> 10 -			
-			
5 -		-	
0 -	200 400 600 800 1000 1200 1400		
	Distance in [ft]		Show Percent Indicates whether the temperature counts
	· ·		should be displayed absolute or in percent.







Pave Project Manager - Pave_2015-09-16-110725.paveproj (Finished on 9/16/2015 9:22 AM) File View Report Extras Options Help			
	Generating Reports		Properties Q ;
4677 966 965 967 966 72837F 232.9ft 67.83365311°W,46.14118346°N (Satellites: 10) Generate Report 52	Post Post Post Post Post Post Tex-244-F Part II Input The Tex-244-F Part II report contains some fields of project description on page 1. You can complete the fields by using this form. You can also leave this form blank. Then the fields in the report are also blank. Report Name Tex 244-F Profile ID 95sb Profile Number Not availbale Status	9 <u>56</u> 9 <u>55</u>	Thermal Profile
Choose a report by name. This will identify the Report Data and Layout.	Tested By Test Location Material Code Material Name Producer		nerates Report
Report name: Detailed Report 9/4/2015 8:48 AM	Area Engineer 2614°N Profile Date 9/16/2015 7:11 AM • Letting Date Not availbale • Controlling CSJ		
261°F 85.6ft 67.83309890°W, 46.14131155°N (Satellites: 11) 968.72	Spec Year Not availbale Spec Item Special Provision Mix Type Project Manager		
	Confirm Inputs and generate report		
033ft Project Properties Time Diagram Speed Diagram Temperature Class Diagram Map diag	ram	1514.11fi • X	-
Servert Read		P	Ignored Sensors Enter the sensor ID you don't want to be displayed. ID 1 is the outer left sensor, Ex.

Generating Reports

Tex 244-F

Thermal Profile Summary Report

Profile ID:	95sb		Profile Date:	9/24/2	015 9:18:13 AM	
Profile Number:			Letting Date:			
Status:			Controlling CSJ:			
County:			Spec Year:			
Tested By:			Spec Item:			
Test Location:	194		Special Provision:			
Material Code:			Mix Type:			
Material Name:			•			
Producer:						
Area Engineer:			Project Manager:			
Course/Lift:	3	Tempo Differe	erature ential Threshold:		25.0	
Segment Length (ft):	: 150	Senso	ors Ignored:		-	
	Therma	l Profile Results	s Summary	·		
Number of Profiles	Mode	erate		Seve	re	
Profiles	25.0°F < differe	ential <= 50.0°F	diffe	erential	ntial > 50.0°F	
28	Number	Percent	Numbe	er	Percent	
20	0	0	0		0	


Profile		g Location		Location	Max Temp	Min Temp	Temperature Differential
INI	Station	GPS in °	Station	GPS in °			Differential
1	194.49	68.12363437 W, 46.11892049 N	193.00	68.12419593 W, 46.11879052 N	303.4	287.8	15.7
2	192.99	68.12419985 W, 46.11878960 N	191.50	68.12476079 W, 46.11866149 N	304.9	289.6	15.3
3	191.49	68.12476285 W, 46.11866104 N	190.00	68.12532427 W, 46.11853654 N	301.1	286.3	14.8
4	189.99	68.12533012 W, 46.11853523 N	188.50	68.12589203 W, 46.11840836 N	299.3	285.8	13.5
5	188.49	68.12589363 W, 46.11840800 N	187.00	68.12645526 W, 46.11828259 N	297.7	285.4	12.2
6	186.99	68.12645906 W, 46.11828176 N	185.49	68.12702186 W, 46.11815402 N	298.9	283.5	15.5
7	185.49	68.12702379 W, 46.11815360 N	183.99	68.12758506 W, 46.11802607 N	302.2	283.8	18.4
8	183.98	68.1275889 W, 46.11802512 N	182.49	68.12815126 W, 46.11789818 N	303.1	292.6	10.4
9	182.49	68.12815319 W, 46.11789773 N	181.00	68.12871395 W, 46.11777111 N	306.1	288.1	18.0
10	180.99	68.12871621 W, 46.11777052 N	179.50	68.12928274 W, 46.11764036 N	302.2	284.4	17.8
11	179.49	68.12928577 W, 46.11763966 N	178.00	68.12985205 W, 46.11751058 N	302.9	287.6	15.3
12	177.99	68.12985387 W, 46.11751020 N	176.50	68.13042113 W, 46.11738235 N	302.0	288.0	14.0
13	176.49	68.13042482 W, 46.11738148 N	175.00	68.13099093 W, 46.11725309 N	301.8	289.2	12.6
14	174.99	68.13099275 W, 46.11725265 N	173.50	68.13155886 W, 46.11712703 N	302.2	288.0	14.2
15	173.49	68.13156263 W, 46.11712618 N	171.99	68.13212684 W, 46.11699931 N	303.6	286.3	17.3
16	171.99	68.13212971 W, 46.11699866 N	170.49	68.13269254 W, 46.11687031 N	302.9	286.5	16.4
17	170.48	68.1326963 W, 46.11686947 N	169.00	68.13325913 W, 46.11674378 N	305.8	288.9	16.9
18	168.99	68.13326314 W, 46.11674285 N	167.50	68.13382973 W, 46.11661558 N	302.0	286.0	16.0
19	167.49	68.13383168 W, 46.11661512 N	166.00	68.1343973 W, 46.11648481 N	298.6	284.2	14.4
20	165.99	68.13440119 W, 46.11648392 N	164.50	68.13497078 W, 46.11635549 N	298.4	282.9	15.5
21	164.49	68.13497271 W, 46.11635503 N	163.00	68.13554162 W, 46.11622699 N	297.5	282.4	15.1
22	162.99	46.1163554551 W, 46.11622616 N	161.49	46.11622099 N 68.13611883 W, 46.11609795 N	296.1	283.6	12.4
23	161.49	46.11622010 N 68.13612069 W, 46.11609752 N	160.00	46.11609795 N 68.13668796 W, 46.11596968 N	301.6	277.2	24.5
24	159.99	68.13669173 W,	158.49	68.13725615 W,	299.7	281.1	18.5
25	158.49	46.11596883 N 68.13725879 W,	157.00	46.11584140 N 68.1378221 W,	301.6	287.4	14.2
26	156.99	46.11584082 N 68.13782589 W,	155.50	46.11571525 N 68.13839327 W,	302.2	288.5	13.7
27	155.49	46.11571440 N 68.13839721 W, 46.11558631 N	154.00	46.11558715 N 68.1389655 W, 46.11545741 N	302.2	289.8	12.4

Summary of Locations Without Thermal Segregation

Generating Reports

Summary of Locations Without Thermal Segregation

	ofile	Beginning	Location	Ending Location		Max Temp	Min Temp	Temperature
	Nr	Station	GPS in °	Station	GPS in °	мах теттр	wiin remp	Differential
2	28	153.99	68.13896866 W, 46.11545670 N	153.24	68.13925736 W, 46.11538960 N	299.1	287.2	11.9



Exporting Data

- Export to .txt (semicolon separated)
- Save as .paveproj





NEXT:

 Data Analyses and Findings: I-95 Rehabilitation; Houlton, ME





Infrared Technology (IR)

Data Analyses and Findings: I-95 Rehabilitation; Houlton, ME

April 28, 2016



AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS



- 1. Project Overview
- 2. Data Collection
- 3. Data Processing
- 4. Data Summary


Northbound and Southbound Lanes; Canadian Border to the South

9/15/15 Start 9/16/15

Start 9/15/15

Google earth

46°08'02.31" N 67°49'23.16" W elev 444 ft







Mixture delivered to site with end dump and horizontal discharge trucks.

Mixture placed with Caterpillar paver and Weiler material transfer vehicle.





Compaction Train:

- Breakdown: Volvo & Ingersoll-Rand Vibratory rollers, & Hamm steel wheel oscillatory roller. Two used in echelon.
- Intermediate; Caterpillar rubber tired roller
- Finish; Caterpillar static steel wheel drum






Four steel wheel rollers used, including: Caterpillar, Volvo & Ingersoll-Rand Vibratory rollers, & Hamm steel wheel oscillatory roller.









- 1. Project Overview
- 2. Data Collection
- 3. Data Processing
- 4. Data Summary


Raw Temperature Profile for first part of the southbound lane.




Raw Temperature Profile for center part of the southbound lane.





Raw Temperature Profile for latter path of the southbound lane.





Raw Temperature Profile showing continuous improvement or more uniform mat temperatures along the southbound lane.












- 1. Project Overview
- 2. Data Collection
- 3. Data Processing
- 4. Data Summary


Data Processing—eliminate invalid temperature measurements:

1. Eliminate measurement locations within 2 feet of the mat's edge.




Data Processing—eliminate invalid temperature measurements:

- 2. Eliminate data with paver stops greater than 10 seconds, between locations:
 - 2 feet behind measurement location of stop
 - 8 feet in front of measurement location of stop
- 3. Eliminate temperature readings < 170 $^{\circ}$ F and > 400 $^{\circ}$ F.




• Temperature Differential, each 150 foot segment



Temperature Differential Criteria, each 150 foot segment:

$$T_{Diff} = T_{98.5} - T_{1.0}$$




- T_{diff} ≤ 25 °F
- $25 \,{}^{\circ}\text{F} < \text{T}_{\text{diff}} \le 50 \,{}^{\circ}\text{F}$
- T_{diff} > 50 °F

No temperature difference

Moderate temperature difference

Severe temperature difference



- 1. Project Overview
- 2. Data Collection
- 3. Data Processing
- 4. Data Summary

Processed Data

Paver Stops	Total Number of	Number of Increments within Temp. Regimes			Thermal Streaking
	Increments	Minor	Moderate	Severe	Streaking
Exclude	579	546	25	8	None
Include	579	494	56	29	None

To include or exclude paver stops? If paver stop cause severe temperature differences: they should be included. However:

Required paver stops due to sampling should be eliminated from temperature difference profiles.

Processed Data

Paver Stops	Total Number of	Number of Increments within Temp. Regimes			Thermal Streaking
	Increments	Minor	Moderate	Severe	Streaking
Exclude	579	546	25	8	None
Include	579	494	56	29	None

Minnesota DOT's specification:

- Minor Temperature Difference: +\$20 per Increment
- Moderate Temperature Difference: \$0 per Increment
- Severe Temperature Difference: -\$20 per Increment

Total Incentive to Contractor: \$9,300 for the project section. [Including paver stops]

In summary: very good temperature consistency along the I-95 Houlton, ME rehabilitation project.



Contact Information:

- Dale Peabody; dale.peabody@maine.gov
- Bruce Yeaton; bruce.yeaton@maine.gov
- Ulrich Amoussou-Guenov; <u>ulrich.amoussou-guenov@maine.gov</u>
- Paul Angerhofer; pangerhofer@moba.de
- Harold Von Quintus; hvonquintus@ara.com
- Paul Dalbey; pdalbey@ara.com





NEXT:

Implementation: Maine DOT and Contractor
 Points of View





Infrared Technology (IR)

Implementation: Maine DOT and Contractor Points of View

April 28, 2015



AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS



Agency/Contractor Deployment

- 1. Agency; Maine DOT
 - Reasons for deploying IR Technology
 - Benefits Agency points of view
 - Plans to implement IR Technology; short-term plans
 - Schedule for deployment
- 2. Contractors: Lane & Pike
 - Reasons for using IR Technology
 - Benefits Contractor points of view
 - Making decisions in real time to minimize penalties
 - Use of future projects

Agency/Contractor Deployment

Some Typical Questions for Deployment:

- 1. How many projects has Pave-IR Scan[™] been used on?
- 2. How many projects were for quality assurance?
- 3. What percent of profiles exhibited medium & severe temperature differences?
- 4. How easy is it to set up the project in Pave-IR ScanTM?
- 5. Any problems experienced with the equipment?
- 6. Has the Pave-IR system changed daily practice?
- 7. Has use of the Pave-IR system changed interaction between the owner & contractor?
- 8. How easy is the IR data to extract and process?
- 9. Do you review the Pave-IR reports at the end of the day?
- 10. Do you think you are getting a higher quality mat at the end of the day using the Pave-IR system?





Infrared Technology (IR)

Implementation Products and Strategies

April 28, 2016




AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS



Implementation Products and Strategies

- 1. Field Demonstration Projects and Products
- 2. Application and Use: Examples
- 3. Questions and Answers



- 1. Case Study/Demonstration Report
- 2. Showcase
- 3. Trouble Shooting and Best Practices Guide
- 4. Specification Guide
- 5. IR Guide/Primer

- 1. Field Demonstration Projects and Case Study Report:
- Purpose
 - Enhance the deployment and use of the IR technology.
 - Identify/summarize lessons learned from field trials.
 - Confirm Pave-IR can identify the different types of temperature differentials that affect mat density and pavement performance.

- 1. Field Demonstration Projects and Case Study Report, continued:
- Outcome
 - Case Study Report
 - Information for showcase
 - Workshops for individual field demonstration projects
 - Demonstrate and discuss value added using IR technology to agency and contractor.

- 2. Showcase:
- Showcase for IR Technology
 - Missouri DOT is the host agency
 - June 1, 2016
- Purpose
 - Highlight IR technology, provide training & operation.
 - Attendance includes agencies, contractors, industry, consultants and academia.
- Outcome
 - Report to document showcase

All participating agencies in IR demonstration projects have received an invitation.

- 3. Trouble Shooting and Best Practices Guide
- Purpose of Guide
 - Provide guidance on:
 - Setting up the equipment and getting started.
 - Interpreting the raw data for making decisions.
 - Identify data collection and maintenance issues with the equipment and software.
- Outcome
 - Based on all 10 demonstration projects
 - Experience of agencies & consultants

4. Specification Guide; AASHTO PP 80-14

Standard Practice for

Continuous Thermal Profile of Asphalt Mixture Construction

AASHTO Designation: PP 80-141



American Association of State Highway and Transportation Officials 444 North Capitol Street N.W., Suite 249 Washington, D.C. 20001

Copylight American Association of State Highway and Transportation Officials Provided by IHS under license with AASHTO No reproduction or networking permitted without license from IHS

- 4. Specification Guide, continued
- Purpose
 - Advance standardization of IR equipment and testing protocols through AASHTO.
 - Agencies can customize it to their needs
- Outcome
 - Revised/Enhanced AASHTO PP 80-14
- Based on:
 - 10 Demonstration Projects
 - Agency Experience: Minnesota DOT, Texas DOT, etc.

- 5. IR Guide/Primer
- Purpose
 - Introduce the Pave-IR method to transportation agencies and contractors.
 - Increase awareness of how IR can improve paving operations and increase uniformity of mat.
 - Demonstrate use of Pave-IR as a QC Tool.
- Outcome
 - Based on all 10 demonstration projects.


Implementation Products and Strategies

- 1. Field Demonstration Projects and Products
- 2. Application and Use: Examples
- 3. Questions and Answers

Application & Use, WHY:

- Continuous readings to evaluate mat uniformity through temperature uniformity.
- Non-uniform temperatures imply non-uniform densities, which usually mean higher maintenance.





Role of IR in Quality Assurance Programs

- 1. Quality control plan; contractor
 - Monitor production/placement operations to minimize temperature differentials of mat.
 - Use data to trouble shoot low or non-uniform densities
- 2. Acceptance plan; agency
 - Reduce future distress and maintenance costs
 - Dispute resolution

IR Role in Quality Control Plan; 3 examples

- 1. Missouri demonstration project
- 2. Virginia demonstration project
- 3. Federal Lands demonstration project

- 1. Missouri demonstration project
 - Communication between plant and paver; monitoring production/placement operations to minimize temperature differentials of mat.





- 2. Virginia demonstration project
 - Identify reason for severe temperature differentials and take action.
 - Avg. temperature differential at start of paving project; about 30 °F.
 - Avg. temperature differential after adding two trucks; about 15 °F.




- 3. Federal Lands demonstration project
 - Identify reason for severe temperature differentials and take action; loading of trucks.
 - One dump of mix in truck bed severe temp. differential
 - Two dump, no stockpile reduced temp. differential.



IR Role in Acceptance Plan; examples:

- Identify cold spots
 - Colorado, Michigan, Minnesota, Quebec, Texas, Washington
- Identify thermal streaks
 - Quebec



Cold spots; areas with increased potential for:

- Fatigue cracks
- Raveling
- Pot holes







Thermal streaks; areas with increased potential for longitudinal cracking.







Specification Guide; AASHTO PP 80-14

- 1. Scope
- 2. Referenced Document
- 3. Terminology
- 4. General Thermal Profile Requirements
- 5. Hardware
- 6. Data File Format
- 7. Calibration
- 8. Profiler Accuracy
- 9. References
- 10. Appendices (Non-mandatory)
 - 1. Example Acceptance Criteria
 - 2. Terminology
 - 3. Criteria
 - 4. Monetary Adjustment

Standard Practice for

Continuous Thermal Profile of Asphalt Mixture Construction

AASHTO Designation: PP 80-141



American Association of State Highway and Transportation Officials 444 North Capitol Street N.W., Suite 249 Washington, D.C. 20001

pyight American Association of State Highway and Transportation Offic vided by IHS under license with AASHTO reproduction or networking permitted without license from IHS

Licenses-Florida Department of Transportation/59030220 Not for Resale, 06/54/2015 13:30:32 MDT

IR Role in Acceptance Plan

- Determine biased areas for sampling and testing
 - Washington DOT
- Determine pay factors
 - Minnesota DOT
 - Quebec
- Minnesota pay factors for each 150 foot segment:
 - \$20 bonus; <25°F
 - \$20 penalty; >50°F

Washington State Department of Transportation

WSDOT SOP 733

Determination of Pavement Density Differentials Using the Nuclear Density Gauge

1. Scope

This test method describes the procedure for locating and testing areas of suspected low cyclic density. Lower pavement density has been related to temperature differentials and areas of "spots, streaks" or visual pavement irregularities. This method uses infrared detection devices and visual inspection to identify areas of potentially low cyclic density.

2. Definitions

- a. Temperature Differential Area- \underline{Any} area where the temperature of the newly placed HMA pavement is greater than 25° F different than the surrounding area.
- b. Aggregate segregation- "Spots, streaks" or visual pavement irregularities in the newly placed HMA pavement that has a significant difference in texture when compared to the surrounding material.
- c. Systematic Density Testing the testing of temperature differential areas or areas of aggregate segregation to determine if there is a pattern of low cyclic density.

3. Equipment

- a. An approved infrared camera OR a handheld noncontact infrared thermometer (features for both should include continuous reading, minimum, maximum, and average readings, laser sighting, and a minimum distance to spot size ratio (D:S) of 30:1.
- b. Nuclear moisture-density gauge
- c. Tape measure.
- d. A can of spray paint for marking test locations.
- e. Required report form.
- 4. Testing Criteria
 - a. Where temperature differentials are 25° F or greater a systematic HMA compaction test is required.
 - b. Where temperature differentials are less than 25° F a systematic HMA compaction test is not required unless, an area shows signs of visual pavement irregularities, surface segregation or a significantly different texture.
- 5. Determination of Systematic Density Testing Locations

Use either and infrared camera or a handheld non-contact infrared device to locate temperature differential areas as follows:

WSDOT Materials Manual M 46-01.07 January 2011 Page 1 of 4

Washington State DOT; WSDOT SOP 733

- Aggregate segregation: spots and streaks defined by visual inspection
- Equipment for measuring temperature differentials:
 - Infrared camera
 - Handheld noncontact infrared device
 - IR-Bar or IR-Scanner not identified
- Temperature Differential Area: > 25°F and paver stops are included
 - Measured prior to compaction
- In temperature differential areas; systematic compaction test is required for all areas.

Alaska DOT; Special Provision draft

- IR and IC added to Glenn Hwy project
- After test strip is completed, monitor is covered for first lot, then removed for latter lots and compared to the first:
 - IR-Scanner
- Temperature Differential Area: > 25°F and paver stops are included
 - Measured prior to compaction
- In temperature differential areas:
 - Perform density profiles
 - Adjust compaction and paving equipment operation to eliminate temperature differential areas.

Texas DOT; Item 341, Tex-244-F

- Equipment for measuring temperature differentials:
 - Infrared camera
 - IR-Bar or IR Scanner
- Temperature Differential Category, behind paver and paver stops are excluded:
 - < 25°F is minor thermal segregation
 - 25°F to 50°F moderate thermal segregation
 - $> 50^{\circ}$ F is severe thermal segregation
- In areas with severe temperature differential:
 - Eliminate or remove and replace.
 - Density profile not required when using IR devices

Minnesota DOT

- Equipment for measuring temperature differentials:
 IR Scanner
- Temperature Differential Category and acceptance:
 - $< 25^{\circ}F$ is minor thermal segregation;
 - 25°F to 50°F moderate thermal segregation
 - $> 50^{\circ}$ F is severe thermal segregation

\$20 bonus/sect.

\$0 bonus

\$20 penalty/sect.

Deployment Strategy, Common Steps/Tasks:

- 1. Define temperature differences that cause significant distress, increasing maintenance cost & reducing service life (Minnesota, Ontario, Texas, Washington).
 - a) Many published reports that document the importance of temp.
- 2. Identify mat property changes between areas with severe temperature differentials (Ontario, Texas).
 - a) Many research reports that identify how density affects the mat's properties related to performance.
- 3. Draft IR specification (Minnesota, Ontario, Texas, Washington)
- 4. Obtain comments from industry for revising specification; getting input from other partners (Ontario, Minnesota, Texas).
- 5. Host/sponsor training sessions with equipment/software


Deployment Strategy, Common Steps/Tasks:

- 6. Execute pilot projects over 1 to 2 years (Minnesota, Ontario)
- 7. Educate industry/agency personnel on results (Ontario).
- 8. Update/revise specification (Minnesota, Ontario, Texas, Washington)
- 9. Establish actions based on temperature profile differences (all)
 - a) Increased density testing (Texas)
 - b) Biased testing (Washington)
 - c) Incentives/disincentives based temperature differentials (Minnesota, Ontario)
- 10. Confirm appropriateness of acceptance plan (Ontario)
- 11. Full deployment

Conclusion from demonstration projects, todate:

 Pave-IR scanner is one tool to confirm a uniform, highquality mat.





Implementation Products and Strategies

- 1. Field Demonstration Projects and Products
- 2. Application and Use: Examples
- 3. Questions and Answers

Agency/Contractor Deployment

Some Questions for Deployment:

- 1. How many projects has Pave-IR Scan[™] been used on?
- 2. How many projects were for quality assurance?
- 3. What percent of profiles exhibited medium & severe temperature differences?
- 4. How easy is it to set up the project in Pave-IR ScanTM?
- 5. Any problems experienced with the equipment?
- 6. Has the Pave-IR system changed daily practice?
- 7. Has use of the Pave-IR system changed interaction between the owner & contractor?
- 8. How easy is the IR data to extract and process?
- 9. Do you review the Pave-IR reports at the end of the day?
- 10. Do you think you are getting a higher quality mat at the end of the day using the Pave-IR system?
- 11. How have agencies/contractors used the IR products?





Complete workshop forms.

NEXT:

Presentation and Demonstration of Ground
 Penetrating Radar Equipment